Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/01/2015-16 Dated: 04-01-2016

# APPROVED TENDER SCHEDULE –'B'

Item No: 59

Name of Work:-Developmental work in GKVK layout and Surrounding area in ward no:04 of Yelahaka Satellite Town Sub Division

| Sl | Description | Unit | Approved Qty | Rate Quoted by the Contractor Approved Rates Sri G VENKATE GOWDA | |
|---|---|---|---|---|---|
| | | | | Rate | Rate in Words |
| 1 | KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2015-16 | Cum | 257.25 | 270.00 | Rupees two hundred seventy only |
| 2 | KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exeeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,HOM of machinery,curing complete as per specifications.Specification no KBS4.1,4.2(item no 4.3,Page no12,PWD SR 2015-16) | Cum | 96.13 | 4800.00 | Rupees four thousand eight hundred only |
| 3 | KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming etc as per specification&direction of the engineer incharge of work (pwd sr2015-16,p.no13,sno4.11) | sqm | 161.15 | 5880.00 | Rupees five thousand eight hundred eighty only |
| 4 | KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specifications.Specification noKBS 4.6.3.TMT bars Fe55 0(pwd sr2015-16,p.no17,s.no4.46) | Qtl | 108.68 | 6602.00 | Rupees six thousand six hundred two only |



| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| | | | 5 | 5.00 | 1.20 | 0.20 | 6.00 | | |
| | | | 1 | 50.00 | 2.00 | 0.20 | 20.00 | | |

| Sl | Description | Unit | Approved Qty | Rate Quoted by the Contractor Approved Rates Sri G VENKATE G... | |
|---|---|---|---|---|---|
| | | | | Rate | Rate in Words |
| 5 | KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters,bittresses,buttresses plinth and string course including cost of all materials,labour complete asperspecificationS.Specification no.KBS 4.6.2(pwd sr2015-16,p.no15/4.31) | Sqm | 580.00 | 300.00 | Rupees three hundred only |

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.